BRUHAT BENGALURU MAHANAGARA PALIKE

TENDER DOCUMENT – KW4

(WORKS COSTING MORE THAN Rs. 100 LAKHS)

Name of Work: - Improvements to roads, drains and other developmental works in Vaderahalli grama panchayathi limits under SWM head in Chief Minister Nava Nagarothan grants of yelahanka division. (Package -9)

Estimate Cost: 1015.00 Lakhs

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

...ngineer
...ngalore – 560064.
Dated : 08-11-2019.

...ATION FOR TENDER (IFT)
(Short term- Tender Notification)
(Two Cover System)
(Through GOK e–Procurement Portal only)

1. The Government of Karnataka, vide **G.O.No.UDD 375 MNY 2018 (ANNEXURE-2,5 & 6) dated 20-09-2019.** has accorded in Principle approval and sanctioned budget under Hon'ble Chief Minister's **"NAVA NAGAROTHAN GRANTS"** for taking up of the works listed below.

2. The Executive Engineer Yelahanka Division invites tenders on behalf of the commissioner, BBMP, Bengaluru from eligible Tenderers for the construction of works detailed in the table below The tenderers may submit tenders for works given in the table through e-procurement portal of the Government of Karnataka (viz https://eproc.karnataka.gov.in).The Tenderers are advised to note the minimum qualification criteria specified in Clause 3 of the Instructions to Tenderers to qualify for award of the contract **as per standard tender document KW-4.**

3. Tenders must be accompanied by Earnest Money Deposit specified for the work in the table below. Earnest money deposit will have to be in any one of the forms as specified in the Tender document (Minimum of Rs1,00,000/- through e-payment under of the following i.e., online / RTGS / NEFT / OTC and the balance by bank guarantee issued by Nationalized / Scheduled Bank and shall have to be valid for 180 days beyond the validity of the tender)

4. Tenders must be submitted online through e-procurement portal on or before 16.00 hours on **28-11-2019** and the opening of tenders will be as per the e-procurement portal guidelines.

5. GST Shall be Paid to the tendered amount separately
6. Other details can be seen in the tender documents.

Sl. No.	Name of the Work	Amount put to tender (Rs. in lakhs)	EMD (Rs. in Lakhs)	Cost of Tender form in Rs. (Non-Refundable)	Period of Completion
1	Improvements to roads, drains and other developmental works in ward no-02 & 03 under road development head in Chief Minister Nava Nagarothan grants of yelahanka division. (Package -01)	832.01	12.50	As per e-Procurement Portal	06 Months (including monsoon)
2	Improvments to roads, drains and other developmental works in Attur ward no-03 under road development head in Chief Minister Nava Nagarothan grants of yelahanka division. (Package -02)	1176.42	15.00	As per e-Procurement Portal	06 Months (including monsoon)
3	Improvements to roads, drains and other developmental works in ward no-03 under road development head in Chief Minister Nava Nagarothan grants	840.25	12.62	As per e-Procurement Portal	06 Months (including monsoon)

EXECUTIVE ENGINEER
YELAHANKA DIV.

For M/s. AGR Projects
CONTRACTOR

	of yelahanka division. (Package -03)				
4	Improvements to roads, drains and other developmental works in ward no-03 & 04 under road development head in Chief Minister Nava Nagarothan grants of yelahanka division. (Package -04)	1188.18	15.00	As per e-Procurement Portal	06 Months (including monsoon)
5	Improvements to roads, drains and other developmental works in Maruthinagara ward no- 01 under SWM head in Chief Minister Nava Nagarothan grants of yelahanka division. (Package -05)	832.00	12.50	As per e-Procurement Portal	06 Months (including monsoon)
6	Improvements to roads, drains and other developmental works in kempegowda ward no- 01 under SWM head in Chief Minister Nava Nagarothan grants of yelahanka division. (Package -06)	840.25	12.60	As per e-Procurement Portal	06 Months (including monsoon)
7	Improvements to roads, drains and other developmental works in Ward No- 01 & 02. under SWM head in Chief Minister Nava Nagarothan grants of yelahanka division. (Package -07)	882.20	13.25	As per e-Procurement Portal	06 Months (including monsoon)
8	Improvements to roads, drains and other developmental works in Ananthapura Attur Ward No- 03 under SWM head in Chief Minister Nava Nagarothan grants of yelahanka division. (Package -08)	840.25	12.60	As per e-Procurement Portal	06 Months (including monsoon)
9	Improvements to roads, drains and other developmental works in Vaderahalli grama panchayathi limits under SWM head in Chief Minister Nava Nagarothan grants of yelahanka division. (Package -09)	852.80	12.79	As per e-Procurement Portal	06 Months (including monsoon)
10	Improvements to roads, drains and other developmental works in Singanayakanahalli grama panchayathi limits under SWM head in Chief Minister Nava Nagarothan grants of yelahanka division. (Package -10)	840.25	12.60	As per e-Procurement Portal	06 Months (including monsoon)
11	Construction of Buildings and other civil works and playgrounds in ward no -01, 03 & 04 under Buildings / Playgrounds / Hospitals head in Chief Minister Nava Nagarothan grants of yelahanka division. (Package -11)	609.10	9.15	As per e-Procurement Portal	12 Months (including monsoon)

NOTE:

1. Pre bid meeting will be held on **18-11-2019** at 15.00 hours in the office of the Chief Engineer (Yelahanka zone) to clarify the issue and to answer questions on any matter that may be raised at that stage as stated in "Instructions to Bidders" of the bidding document.
2. Technical Bids will be opened on the website https://eproc.karnataka.gov.in in the office of the Executive Engineer -Yelahanka Division on **30-11-2019** at **16.00** hours.
3. Aspiring Bidders/Contractors who have not registered in e-procurement should register before participating through the website https://eproc.karnataka.gov.in
4. Before submission of online bids, bidders must ensure that scanned copies of all the necessary documents have been attached with bid.

For M/s. ACR Projects
CONTRACTOR
Proprietor

EXECUTIVE ENGINEER
YELAHANKA DIV

3.6 Tenderers who meet the above specified minimum qualifying criteria, will only be qualified, if their available tender capacity is more than the total tender value. The available tender capacity will be calculated as under:

Where **Assessed available tender capacity = (A*N*1.5- B)**

A = Maximum value of civil engineering works executed in any one year during the last five years *(updated to* **2019-2020** *price level)* taking into account the completed as well as works in progress.
N = Number of years prescribed for completion of the works for which tenders are invited.
B = Value, at **2019-2020** price level, of existing commitments and on-going works to be completed during the next **09 months**

Note: ***The statements showing the value of existing commitments and on-going works as well as the stipulated period of completion remaining for each of the works listed should be countersigned by the Employer in charge, not below the rank of an Executive Engineer or equivalent.***

3.7 Even though the Tenderers meet the above criteria, they are subject to be disqualified if they have:

- made misleading or false representations in the forms, statements and attachments submitted in proof of the qualification requirements; and/or
- Record of poor performance such as abandoning the works, not properly completing the contract, inordinate delays in completion, litigation history, or financial failures etc.; and/or
- participated in the previous Tender for the same work and had quoted unreasonably high tender prices and could not furnish rational justification.

4. One Tender per Tenderer:

4.1 Each tenderer shall submit only one tender for one package. A tenderer who submits or participates in more than one Tender (other than as a sub-contractor or in cases of alternatives that have been permitted or requested) will cause all the proposals with the Tenderer's participation to be disqualified.

5. Cost of Tendering:

5.1 The tenderer shall bear all costs associated with the preparation and submission of his tender, and the Employer will in no case be responsible and liable for those costs.

6. Site visit:

6.1 The Tenderer at his own responsibility and risk is encouraged to visit and examine the Site of Works and its surroundings and obtain all information that may be necessary for preparing the Tender and entering into a contract for construction of the Works. The cost of visiting the Site shall be at the Tenderer's own expense.

B. Tender documents

7. Content of Tender documents

7.1 The set of tender documents shall have all the Sections given in Page 2.
7.2 Both the sets should be completed and returned with the tender.

8. Clarification of Tender Documents

8.1 A prospective tenderer requiring any clarification of the tender documents may notify the Employer in writing or by cable (hereinafter "cable" includes telex and facsimile) at the Employer's address indicated in the invitation to tender. The Employer will respond to any request for clarification which he receives earlier than 15 days prior to the deadline for submission of tenders. Copies of the

For M/s. ACR Projects
CONTRACTOR
Proprietor

EXECUTIVE ENGINEER
YELAHANKA DIV

17. **Late Tenders**

17.1 Any Tender received by the Employer after the deadline prescribed in Clause 16 will be returned unopened to the Tenderer.

18. **Modification and Withdrawal of Tenders**

18.1 Tenderers may modify contents of First or Second Covers separately for each Cover or withdraw their Tenders by giving notice in writing before the deadline prescribed in Clause 16.

18.2 Each Tenderer's modification separately for each Cover or withdrawal notice shall be prepared, sealed, marked, and delivered in accordance with Clause 14 & 15, with the outer and inner envelopes additionally marked **"MODIFICATION FOR FIRST/SECOND COVER"** or **"WITHDRAWAL"**, as appropriate.

18.3 No Tender may be modified after the deadline for submission of Tenders.

18.4 Withdrawal or modification of a Tender between the deadline for submission of Tenders and the expiration of the original period of Tender validity specified in Clause 12.1 above or as extended pursuant to Clause 12.2 may result in the forfeiture of the earnest money deposit pursuant to Clause 13.

18.5 Tenderers may only offer discounts to, or otherwise modify the prices of their Tenders by submitting Tender modifications in accordance with this clause, or included in the original Tender submission.

E. Tender opening and evaluation

19. **Opening of First Cover of all Tenders and evaluation to determine qualified Tenderers:**

19.1 The Employer will open the First Covers of all the Tenders received (except those received late or withdrawn), including modifications for First Cover made pursuant to Clause 18, in the presence of the Tenderers or their representatives who choose to attend on **30-11-2019at 16.00 hours** on the date and the place specified in Clause 16. In the event of the specified date of Tender opening being declared a holiday for the Employer, the Tenders will be opened at the appointed time and location on the next working day.

19.2 Envelopes marked **"WITHDRAWAL"** shall be opened and read out first. The First Cover of Tenders for which an acceptable notice of withdrawal has been submitted pursuant to Clause 18 shall not be opened.

19.3 The Tenderers names, the presence or absence of earnest money deposit (amount, format and validity), the submission of qualification information and such other information as the Employer may consider appropriate will be announced by the Employer at the opening. Late and withdrawn Tenders will be returned unopened to tenders.

19.4 The Employer shall prepare minutes of the Tender opening, including the information disclosed to those present in accordance with Sub-Clause 19.3.

19.5 The Second Cover of all the Tenderers including modifications for Second Cover shall be placed in a large cover and securely sealed in the presence of the tenderers or their representatives, who are present and also get the same signed by all those tenderers or their representatives. The large cover shall be kept in safe custody by the Employer.[4]

19.6 The Employer will evaluate and determine whether each tender (a) meets the eligibility criteria defined in ITT Clause 2; (b) is accompanied by the required earnest money deposit as per stipulations in ITT Clause and (c) meets the minimum qualification criteria stipulated in ITT Clause 3. The Employer will draw out a list of qualified Tenderers.[5]

---

[4] **Refer GOK circular No. PWD 1359 SO/FC 2001 (P-2) dated 30th June 2003.**

[5] The evaluation of the technical aspects contained in the first cover should be completed within a reasonable period and the time gap between the opening of the first and second cover should be the minimum and in any case not more than 45 days {In exceptional cases, approval of the Secretary (Works)

For M/s. ACR Projects

CONTRACTOR

Proprietor

EXECUTIVE ENGINEER
YELAHANKA DIV

Principal place of business: _____ (Attach Copy)

1.2 Total value of civil engineering construction works executed and payments received in the last five years (in Rs. Lakhs) Attach Certificate from Chartered Accountant

2015 - 16 .....
2016 - 17 .....
2017 - 18 .....
2018 - 19 .....
2019 - 20 .....

1.3 Work performed as Prime Contractor (in the same name) on works of similar nature over during the five years specified in 1.2 above.

Project Name	Name of Employer	Descrip-tion of Work	Contract Number	Value of Contract Rs. Lakhs	Date of issue of work order	Specified period of completion	Actual date of Actual date of	Remarks explaining reasons for delay in completion of work
1	2	3	4	5	6	7	8	9

1.4 Quantities of work executed as prime contractor (in the same name) during the last five years specified in 1.2 above:

Year	Name of Work	Name of Employer	Quantity of work performed (cum)[7]			Remarks (Indicate contract reference)
			Cement Concrete	Masonry	Earthworks	
2015-16						
2016-17						
2017-18						
2018-19						
2019-20						

1.5 Information on works for which Tenders have been submitted and works which are yet to be completed as on the date of this Tender.

(A) Existing commitments and on-going works:

Description of Work	Place & State	Contract No. & Date	Name And Address of Employer	Value of Contract (Rs. lakhs)	Stipulated period of completion	Value of works remaining to be completed (Rs. lakhs) Attach Certificates from Engineers -in-Charge	Anticipated date of completion
1	2	3	4	5	6	7	8

(B) Works for which Tenders already submitted:

Description of Work	Place & State	Name and Address of Employer	Estimated value of works (Rs. lakhs)	Stipulated period of completion	Date when decision is expected	Remarks if any
1	2	3	4	5	6	7

1.6. The following items of equipment are considered essential for successfully carrying out the works. The Tenderer should furnish all the information listed below.

[7] Items of work for which data is requested should tally with that specified in ITT Clause 3

For M/s. ACR Projects
CONTRACTOR
Proprietor

EXECUTIVE ENGINEER
YELAHANKA DIV

3. The Employer hereby covenants to pay the Contractor in consideration of the execution and completion of the Works and the remedying the defects wherein the Contract Price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.

4. The following documents shall be deemed to form and be read and construed as part of this Agreement, viz:

i) Letter of Acceptance;
ii) Notice to proceed with the works;
iii) Contractor's Tender;
iv) Contract Data;
v) Conditions of contract (including Special Conditions of Contract);
vi) Specifications;
vii) Drawings;
viii) Bill of Quantities; and
ix) Any other document listed in the Contract Data as forming part of the contract.

In witness whereof the parties thereto have caused this Agreement to be executed the day and year first before written.

The Common Seal of

.....

Signed, Sealed and Delivered by the said

.....

.....

in the presence of:

Binding Signature of Employer

.....

Binding Signature of Contractor

.....

SECTION 5: CONDITIONS OF CONTRACT

Table of Contents

			Page No.
A.	**General**		
	1. Definitions		25
	2. Interpretation		25
	3. Law governing contract		26
	4. Employers decisions		26
	5. Delegation		26
	6. Communications		26
	7. Subcontracting		26
	8. Other Contractors		26
	9. Personnel		26
	10. Employer's and Contractor's risks		26
	11. Employer's risks		26
	12. Contractor's risks		26
	13. Insurance		27
	14. Site Investigation Report		27
	15. Query about Contract Data		27
	16. Contractor to construct the Works		27
	17. The Works to be completed by Intended Completion Date	28	27
	18. Approvals by the Employer		
	19. Safety		28
	20. Discoveries		28
	21. Possession of the Site		28
	22. Access to the Site		28
	23. Instructions		28
	24. Procedure for resolution of disputes	28	28
B.	**Time Control**		
	25. Program		29
	26. Extension of the Intended Completion Date		29
	27. Delays ordered by the Employer	29	29
	28. Management meetings		29

For M/s. ACR Projects
CONTRACTOR
Proprietor

EXECUTIVE ENGINEER
YELAHANKA DIV

31.1 The Employer shall give notice to the Contractor of any Defects before the end of the Defects Liability Period, which begins at Completion and is defined in the Contract Data. The Defects

31.2 Liability Period shall be extended for as long as Defects remain to be corrected.
Every time notice of a Defect is given, the Contractor shall correct the notified Defect within the length of time specified by the Employer's notice.

32. Uncorrected defects

32.1 If the Contractor has not corrected a Defect within the time specified in the Employer's notice, the Employer will assess the cost of having the Defect corrected, and the Contractor will pay this amount.

33. Bill of Quantities (BOQ) **COST CONTROL**

33.1 The BOQ shall contain items for the construction, installation, testing, and commissioning work to be done by the Contractor.

33.2 The BOQ is used to calculate the Contract Price. The Contractor is paid for the quantity of the work done at the rate in the BOQ for each item

34. Variations

34.1 The Employer shall have power to order the Contractor to do any or all of the following as considered necessary or advisable during the progress of the work by him
(a) Increase or decrease of any item of work included in the Bill of Quantities (BOQ);
(b) Omit any item of work;
(c) Change the character or quality or kind of any item of work;
(d) Change the levels, lines, positions and dimensions of any part of the work;
(e) Execute additional items of work of any kind necessary for the completion of the works; and
(f) Change in any specified sequence, methods or timing of construction of any part of the work.

34.2 The Contractor shall be bound to carry out the work in accordance with any instructions in this connection, which may be given to him in writing by the Employer and such alteration shall not vitiate or invalidate the contract.

34.3 Variations shall not be made by the Contractor without an order in writing by the Employer, provided that no order in writing shall be required for increase or decrease in the quantity of an item appearing in the BOQ so long as the work executed conforms to the approved drawings.

34.4 The Contractor shall promptly request in writing to the Employer to confirm verbal orders and the officer issuing oral instructions shall confirm it in writing within 30 days, failing which the work shall be carried out as though there is no variation. In case variation is approved it shall be accompanied by BOQ, failing which the contractor shall be responsible for deviation if any. Further, approval of Govt. / BBMP has to be obtained for the variation exceeding 5%.

35. Payments for Variations

35.1 Payment for increase in the quantities of an item in the BOQ up to 25% of that provided in the Bill of Quantities shall be made at the rates quoted by the Contractor.

35.2 For quantities in excess of 125% of the tendered quantity of an item as given in the BOQ, the Contractor shall be paid at the rate entered in or derived from in the Schedule of Rates (applicable for the area of the work and current at the time of award of contract) plus or minus the overall percentage of the original tendered rates over the current Schedule of Rates prevalent at the time of award of contract.

35.3 If there is no rate for the additional, substituted or altered item of the work in the BOQ, efforts would be made to derive the rates from those given in the BOQ or the Schedule of Rates (applicable for the area of the work and current at the time of award of contract) and if found feasible the payment would be made at the derived rate for the item plus or minus the overall percentage of the original tendered rates over the current Schedule of Rates prevalent at the time of award of contract

35.4 If the rates for additional, substituted or altered item of work cannot be determined either as at 35.1 or 35.2 or 35.3 above, the Contractor shall be requested to submit his quotation for the items supported by analysis of the rate or rates claimed, within 7 days.

35.5 If the Contractor's quotation is determined unreasonable, the Employer may order the Variation and make a change to the Contract Price which shall be based on Employer's own forecast of the effects of the Variation on the Contractor's costs.

For M/s. ACR Projects
Proprietor

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

contract, and less taxes due to be deducted at source as per applicable law and make payment accordingly.

51. Property

51.1 All materials on the Site, Plant, Equipment, Temporary Works and Works are deemed to be the property of the Employer, if the Contract is terminated because of a Contractor's default.

52. Release from performance

52.1 If the Contract is frustrated by any event entirely outside the control of either the Employer or the Contractor the Employer shall certify that the Contract has been frustrated. The Contractor shall make the Site safe and stop work as quickly as possible after receiving this certificate and shall be paid for all work carried out before receiving it and for any work carried out afterwards to which commitment was made

F. Special Conditions of Contract

1. Labour:

The Contractor shall, unless otherwise provided in the Contract, make his own arrangements for the engagement of all staff and labour, local or other, and for their payment, housing, feeding and transport.

The Contractor shall, if required by the Employer, deliver to the Employer a return in detail, in such form and at such intervals as the Employer may prescribe, showing the staff and the numbers of the several classes of labour from time to time employed by the Contractor on the Site and such other information as the Employer may require.

2. Compliance with labour regulations

During continuance of the contract, the Contractor shall abide at all times by all existing labour enactments and rules made there under, regulations, notifications and bye laws of the State or Central Government or local authority and any other labour law (including rules), regulations, bye laws that may be passed or notification that may be issued under any labour law in future either by the State or the Central Government or the local authority. The Contractor shall keep the Employer indemnified in case any action is taken against the Employer by the competent authority on account of contravention of any of the provisions of any Act or rules made there under, regulations or notifications including amendments. If the Employer is caused to pay or reimburse, such amounts as may be necessary to cause or observe, or for non-observance of the provisions stipulated in the notifications/bye laws/Acts/Rules/regulations including amendments, if any, on the part of the Contractor, Employer shall have the right to deduct any money due to the Contractor including his amount of security deposit. The Employer shall also have right to recover from the Contractor any sum required or estimated to be required for making good the loss or damage suffered by the Employer.

The employees of the Contractor in no case shall be treated as the employees of the Employer at any point of time

3. Protection of Environment:

The contractor shall take all reasonable steps to protect the environment on and off the Site and to avoid damage or nuisance to persons or to property of the public or others resulting from pollution, noise or other causes arising as a consequence of his methods of operation. During continuance of the contract, the contractor shall abide at all times by all existing enactments on environmental protection and rules made there under, regulations, notifications and bye-laws of the State or Central Government, or local authorities and any other law, bye-law, regulations that may be passed or notification that may be issued in this respect in future by the State or Central Government or the local authority.

4. Arbitration (Clause 24)

4.1 The procedure for arbitration shall be as follows:

(a) In case of dispute or difference arising between the Employer and the Contractor relating to any matter arising out of or connected with this agreement it shall be settled in accordance with

For M/s. ACR Projects
Proprietor

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

The Employer is:

Name: The Commissioner
Address: BBMP, N.R. Square Bangalore-02 [1.1]
Name of authorized Representative: Executive Engineer
Yelahanka Division
CMC road Yelahanka old town
BBMP, Bangalore – 560064.

The name and identification number of the Contract is [1.1]

Improvements to roads, drains and other developmental works in Vaderahalli grama panchayathi limits under SWM head in Chief Minister Nava Nagarothan grants of yelahanka division. (Package -9)

Sl.No	Name of the Work
1	Improvements to roads and drains at vaderahalli layout
2	Improvements to roads and drains at vaderahalli Rainbow layout
3	Improvements to roads and drains at Muneshwara layout
4	Improvements to roads and drains at Medi agrahara village
5	Improvements to roads and drains at Medi agrahara nirashrithara layout
6	Improvements to roads and drains at Syampura village.
7	Improvements to roads and drains at subedarapalya village.
8	Improvements to roads and drains at Veerasagara village

The Works consist of Formation of Roads, Construction of footpath, Drains & Asphalting

The start date shall be the date of issue of notice to proceed with the work. [1.1]

The Intended Completion Date for the whole of the Works is **6 months**[12] with the following milestones [17, 26]

Milestone dates:
Physical works to be completed Period from the date of issue of Notice to proceed with the work

Milestone 1 i.e Financial Progress for Rs.2.81 Crores within 02 Months from the date of work order
Milestone 2 i.e Financial Progress for Rs.5.62 Crores within 04 Months from the date of work order
Milestone 3 i.e Financial Progress for Rs. 8.52 Crores within 06 Months from the date of work order

The Site Possession Date is:[13] **Date of work order**

[21]

[12] At the time of preparation of the tender document give the period required for completion of whole work and the milestones. When the Agreement is drawn after award of contract the dates can be put in.
[13] At the time of preparation of the tender document give the period after the issue of work order, when the site would be made available to the contractor, for example 'one week after the issue of work order'.

For M/s. ACR Projects
CONTRACTOR
Proprietor

EXECUTIVE ENGINEER
YELAHANKA DIV

for failing to supply "as built" drawings or supply of ... of the (68)

and Maintenance Manuals by the date required is Rs 1,000,000/-

(The amount should be sufficient to get the completion drawings or Operating and Maintenance Manuals prepared by alternative agency in case the contractor fails to submit.) (68)

The following events shall also be fundamental breach of the contract:

1. The contractor has contravened Sub-clause 7.1 and Clause 9 of CC. (69.2)

The percentage to apply to the value of the work not completed representing the Employer's Additional cost for completing the Works shall be 30 percent (30%). (50.1)

(If merger if need be. It should be sufficient to get the balance of works completed by alternative agency)

SECTION 7: SPECIFICATIONS

As per specifications mentioned in BOQ

SECTION 8: DRAWINGS
(Enclosed)
SECTION 9: BILL OF QUANTITIES

Sl No	Description of Item	Unit	Total Quantity	Rates in Rs	
				Rate in figures	Rate in words
1	KSBRR 306-1 Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed the disposed earth to be levelled neatly after breaking of clods complete as per specifications. (1 No-19 LP No-HD, 10m lead - 11.28x2x119.57)	Cum	6570.55		
2	Filling in foundation with granite/trap broken metal 100mm size down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with lead up to 50m and lift 1.5m complete as per specifications. Data Rate				
	a) 40mm Jelly	Cum	5.33		
	b) 20mm Jelly	Cum	5.33		
	c) Coarse sand	Cum	4.00		
	d) Fine Sand	Cum	2.67		
	e) 12.5mm chips	Cum	4.00		

37 Score out which ever is not applicable.

For M/s. AGR Engineers
Proprietor

EXECUTIVE ENGINEER
YELAHANKA

3	Supplying, laying and jointing HDPE pipes of specified grade and conforming to IS 4984- 995 with latest amendments and conveyingto work site including loading and unloading at both destinations and rolling and lowering into trenches, laying true to line and jointing of pipes and specials, giving hydraulic test as per relevant ISS with all lead and lifts including encasing the pipe alround to a depth of not less than 15 cms. with soft gravel or selected earth available from the excavation, testing and commissioning. The rate is exclusive of required specials and fittings wherever necessary like saddle Tee, stub ends, flanged sets, bends, reducers etc. complete (Contractor will make his own arrangements for procuring water for testing) etc. for : HDPE Grade PE80-PN6.0, 630 mm dia. (Perforated Pipe for Rain Water Harvesting Pit) (BWSSB SR 2017-18, Pg No 121 Item No. 1.17 Code No. K010Q)	m	77.40		
4	Providing of Geonets for Rain Water Harvesting pit on top of the filter media as specified in drawings or as approved by Engineer Incharge. Data Rate	Sqm	13.33		
5	KSRB 4-1.2 Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete land in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM curing complete as per specifications. (P No-13,I No-4.2 KPWD SR 2018-19)	Cum	1006.68		
6	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200, including cost of materials, labour, HOM complete as per specificationsdo- Wall & bottom thickness 15cm (I No-37.59.2 P No-271 KPWD SR 2018-19)	Cum	2085.48		
7	KSRRB M2200-6 Providing T M T steel reinforcement for R C C work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification MORTH Specification No.1600 & 2200(I No-28.8.2 P No-229)	Ton	131.53		
8	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting , including form work, cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc complete. (Data Rate)	Sqm	5113.20		
9	Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge. (Data Rate)	Sqm	459.90		
10	KSRRB M300-14 Excavation for roadwork in all types of soil by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and complete as per specifications MORTH Specificatio MORTH Specification No.3011Loading and unloading with 10km lead= (I No-19.14.P No-143) 10km lead = (1.28x2x8)	Cum	8754.90		
11	KSRRB 300-58 Compaction of original ground by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM complete as per specifications MORTH / Chapter 3 (I No-19.64,P No-147)	Sqm	28261.50		

For M/s. ACR Projects
CONTRACTOR
Proprietor

EXECUTIVE ENGINEER
YELAHANKA DIV

-We hereby waive the necessity of your demanding the said debt from the Contractor before presenting us with the demand.

We further agree that no change or addition to or other modification of the terms of the Contract or of the Works to be performed there under or of any of the Contract documents which may be made between you and the Contractor shall in any way release us from any liability under this guarantee, and we hereby waive notice of any such change, addition or modification.

This guarantee shall be valid until 30 days from the date of expiry of the Defects Liability Period.

Signature and seal of the guarantor _____
Name of Bank _____
Address _____
Date _____

Page No 01 ಅಂದ 42 ರವರೆಗೆ
KW-4 tender document
ಕಛೇರಿಯಿಂದ ಪಡೆಯಲಾಗಿದೆ

Executive Engineer
B.B.M.P Division
Yelahanka

EXECUTIVE ENGINEER
YELAHANKA DIV